

# Climate Change Impacts on the Housing Infrastructure at Oneida Nation of the Thames

July 24, 2018



Project No. 163401448

Prepared by:



Developed in partnership with:



## Sign-off Sheet

This document entitled **Climate Change Impacts on the Housing Infrastructure at Oneida Nation of the Thames** was prepared by Stantec Consulting Ltd. ("Stantec") for the account of Ontario First Nations Technical Services Corporation (the "Client"). Any reliance on this document by any third party is strictly prohibited. The material in it reflects Stantec's professional judgment in light of the scope, schedule and other limitations stated in the document and in the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. In preparing the document, Stantec did not verify information supplied to it by others. Any use which a third party makes of this document is the responsibility of such third party. Such third party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third party as a result of decisions made or actions taken based on this document.

| Prepared by              |             |
|--------------------------|-------------|
|                          | (signature) |
| Guy Félio, Ph.D., P.Eng. |             |
|                          |             |
| Reviewed by              |             |
|                          | (signature) |
| Jordan Stewart, P.Eng.   |             |
|                          |             |
| Approved by              |             |
|                          | (signature) |

Wayne L.E. Penno, MBA, P.Eng

# **Table of Contents**

| EXEC                            | CUTIVE SUMMARY   | I                                      |
|---------------------------------|--|--|
| ABBI                            | REVIATIONS   |  |
| <b>1.0</b><br>1.1<br>1.2<br>1.3 | INTRODUCTION<br>COMMUNITY DESCRIPTION<br>SCOPE OF THE STUDY<br>PROJECT TIMELINE  | 1.1<br>1.2<br>1.3                      |
| 1.4                             | PROJECT TEAM   | 1.3                                    |
| <b>2.0</b><br>2.1               | STEP 1: PROJECT DEFINITION<br>CLIMATE RELATED CONCERNS   |  |
| 2.2<br>2.3                      | PHYSICAL ASSETS TO BE CONSIDERED<br>TIME HORIZON FOR THE STUDY   |  |
| 3.0                             | STEP 2: DATA COLLECTION  | 3.1                                    |
| 3.1<br>3.2                      | INVENTORY OF INFRASTRUCTURE COMPONENTS   | 3.1<br>3.1<br>3.4<br>3.5<br>3.6<br>3.7 |
| 3.3                             | CLIMATE CONSIDERATIONS         3.3.1       Climate Trends and Projections         3.3.2       Climate Elements Considered to Affect the Infrastructure | 3.9                                    |
| 4.0                             | STEP 3: RISK ASSESSMENT  | 4.1                                    |
| 4.1                             | RISK THRESHOLDS  |  |
| 4.2                             |  |  |
| 4.3<br>4.4                      | CLIMATE PROBABILITY SCORING<br>INFRASTRUCTURE SEVERITY SCORING   |  |
| 4.4                             | RISK ASSESSMENT  |  |
| 1.0                             | <ul> <li>4.5.1 Infrastructure Components Evaluated</li> <li>4.5.2 Risk Screening Process</li></ul>   | 4.5<br>4.6                             |
| 4.6                             | COMMUNITY IMPACTS FROM INFRASTRUCTURE RISKS  | 4.9                                    |
| 5.0                             | CONCLUSIONS AND RECOMMENDATIONS  | 5.1                                    |

### LIST OF FIGURES

| Figure 1: Satellite view of Oneida and surrounding area (Source: Google Earth)        | 1.2  |
|---|------|
| Figure 2. Front View of Entrance Senior Citizens Complex                              |      |
| Figure 3. View of Front Individual Units of Senior Citizens Complex                   | 3.2  |
| Figure 4. Side View of Senior Citizens Complex with Propane Tanks                     | 3.2  |
| Figure 5. View of the Back Units of the Senior Citizens Complex                       |      |
| Figure 6. Back-up Generator at the Senior Citizens Complex                            |      |
| Figure 7. Front View of Quadplex  |      |
| Figure 8. Rear View of Quadplex   |      |
| Figure 9. Quadplex Roof: Metal and Asphalt Shingles                                   |      |
| Figure 10. Duplex: Angle View   |      |
| Figure 11. Duplex: Side and Back View   |      |
| Figure 12. Single Family Unit #1  |      |
| Figure 13. Single Family Unit #2  |      |
| Figure 14. Single Family Unit #3  |      |
| Figure 15. Single Family Unit #4  |      |
| Figure 16: Standing Stone School Entrance (Source: https://oneida.on.ca/standing-     | -    |
| stone-school/)  | 3.8  |
| Figure 17. Satellite View of Standing Stone School (Source: Google Earth)             |      |
| Figure 18. Average monthly temperature and precipitation from St. Thomas WPCP         |      |
|   | 3.9  |
| Figure 19. Mean Daily Temperature for Summer - Historical Trend and Future Climate    |      |
| Projection (St. Thomas Weather Station, RCP 4.5)                                      | 3.11 |
| Figure 20. Mean Daily Temperature for Winter - Historical Trend and Future Climate    |      |
| Projection (St. Thomas Weather Station, RCP 4.5)                                      | 3.11 |
| Figure 21. Summer Precipitation - Historical Trend and Future Climate Projection (St. |      |
| Thomas Weather Station, RCP 4.5)  | 3.12 |
| Figure 22. Winter Precipitation - Historical Trend and Future Climate Projection (St. |      |
| Thomas Weather Station, RCP 4.5)  | 3.12 |
| Figure 23. Winter Rain Events   |      |
| Figure 24. Cooling Degree Days - Current and Future Climate Projection (St. Thomas    |      |
| Weather Station, RCP 4.5)   | 3.14 |
| Figure 25. Heating Degree Days - Current and Future Climate Projection (St. Thomas    |      |
| Weather Station, RCP 4.5)   | 3.15 |
| Figure 26. Tornado Records within 50km of St. Thomas                                  |      |
| Figure 27: FN PIEVC Protocol Risk Assessment Process Flowchart                        |      |
| Figure 28. Photo to Project Team having completed the Infrastructure Severity Scoring |      |
| table at Workshop 3 on November 16, 2017 (Photo by Guy Félio)                         | 4.4  |

### LIST OF TABLES

| Table 1: Timeline for the Project   | 1.3  |
|---|------|
| Table 2. Project Team   |      |
| Table 3. Historical IDF - Accumulated Precipitation (mm)                            | 3.13 |
| Table 4. Projected 2050s IDF (2025 - 2075 average) - Accumulated Precipitation (mm) | 3.14 |
| Table 5: Principal Climate Elements Selected by the Project Team for the Analysis   | 3.16 |
| Table 6: Risk Thresholds  | 4.1  |
| Table 7: FN PIEVC Probability Scoring   | 4.2  |
| Table 8: Probability Scores for Selected Climate Events                             | 4.3  |
| Table 9: Infrastructure Severity Scoring Developed by the Project Team              | 4.5  |
| Table 10: Infrastructure Assessed   | 4.6  |
| Table 11: Summary of Moderate and High Risks  | 4.8  |
| Table 12. Risk Mitigation and Adaptation Measures recommendations                   | 5.2  |

### LIST OF APPENDICES

| APPENDIX A | WORKSHOP PRESENTATIONSA.1 |
|------------|---------------------------|
|------------|---------------------------|

## **Executive Summary**

This report presents the results of the Climate Risk Assessment (CRA) study conducted for the housing infrastructure in the Oneida Nation of the Thames community using the Ontario First Nations Technical Services Corporation (OFNTSC) First Nations PIEVC Protocol; a methodology adapted from Engineers Canada's Public Infrastructure Engineering Vulnerability Committee (PIEVC) Engineering Protocol [https://pievc.ca/protocol]. The report identifies infrastructure vulnerabilities to current and future severe weather; focusing on different types of housing units. The report establishes a risk profile for the assessed infrastructure and provides recommendations regarding mitigating the risks with the highest consequences.

The methods utilized to develop the report include reviewing background information (such as climate data, infrastructure drawings and existing infrastructure condition reports) and consultation with local personnel (such as Oneida's Housing Coordinator, Environment Services and Public Works staff). The input from local expertise regarding the housing is combined with the background information to develop a risk profile, in the form of a matrix, highlighting assets that may be most at risk under current climate conditions, with respect to specific weather events. The findings under current climate conditions are then re-evaluated against the demands that may be placed on them under future climate scenarios, with respect to the expected change of frequency or intensity of specific weather events.

The results of this process suggest that for the infrastructure identified, under current climate conditions, there are 54 interactions between a selected infrastructure item and a particular weather event that are categorized with a "Moderate" risk threshold rating. Another 16 interactions are categorized with a "High" risk threshold rating. When evaluated against projected future climate conditions, the count of these categories of risk threshold become 57 for "Moderate" and 37 for "High".

The housing assets, school and infrastructure that provide services of the Oneida Nation of the Thames are generally well maintained and provide safe services to the community. The Oneida Council, under budget pressures, has managed to maintain these assets in a state of good repair; the maintenance practices they have adopted and implemented have resulted in resilient infrastructure.

The findings reinforce the need for regular maintenance and property ownership practices and for sound asset management planning for infrastructure. The specific Risk Mitigation and Adaptation Measures recommended for Oneida generally fall into the following categories:

- Considerations to include future climate impacts in the design and construction practices of new housing assets and infrastructure
- Additional monitoring, inspection and maintenance of housing assets and infrastructure conditions by Operations personnel
- Emergency preparedness in case of infrastructure failures, such as back-up power and supplies, and/or exploring arrangements with neighbouring communities for emergency support

• Additional training of Operations personnel and providing them with proper safety equipment when work is required in hazardous conditions.

This report also acknowledges the fact that the analysis conducted has limitations. The intent of the study is to provide an overall risk profile of the housing assets owned and managed by the Oneida Nation of the Thames; the recommendations do not address specific housing or infrastructure issues. This report should not be solely relied upon as a plan to make the housing assets of the Oneida Nation of the Thames more resilient to changes in climate. Rather this report provides a starting point for identifying specific assets and infrastructure that presents the greatest risks in terms of service to the community, and helps identify the assets that deserve a detailed analysis to ensure they can continue effectively and safely serving the Oneida Nation of the Thames in the coming decades.

# Abbreviations

| ACRS   | Asset Condition Reporting System                            |
|--------|---|
| CRA    | Climate Risk Assessment                                     |
| СОО    | Chiefs of Ontario   |
| GHG    | Green House Gas   |
| ICMS   | Integrated Capital Management System                        |
| INAC   | Indigenous and Northern Affairs Canada                      |
| IPCC   | Intergovernmental Panel on Climate Change                   |
| O&M    | Operations and Maintenance                                  |
| OCCIAR | Ontario Centre for Climate Impacts and Adaptation Resources |
| OFNTSC | Ontario First Nations Technical Services Corporation        |
| PIEVC  | Public Infrastructure Engineering Vulnerability Committee   |
| PLC    | Programmable Logic Controller                               |
| SCADA  | Supervisory Control and Data Acquisition                    |
| WTP    | Water Treatment Plant (potable water)                       |
| WWTP   | Wastewater Treatment Plant                                  |

Introduction July 24, 2018

# **1.0 INTRODUCTION**

Severe weather and climate uncertainty represent risks to public safety in Canada and around the world, as well as to the safety of engineered systems and the services they provide. In this context, an increasing number of public agencies and organizations that provide public services address climate change adaptation as part of their primary mandate—protecting the public interest, which includes life, health, property, economy, culture and the environment.

The impacts of severe weather add to the existing stresses on infrastructure and the services it provides. In addition to factors that reduce the capacity and performance of these assets (e.g. age, increased demand, material weathering, design and construction inadequacies, lack of maintenance, or extension of service life beyond design), the increased intensity of weather events can produce an incremental load that can cause asset failure.

Infrastructure vulnerability and risk assessments are the foundations to ensure climate change is considered in engineering design, operations and maintenance of community infrastructure, buildings, and facilities. Taking the time to identify the services and related assets that are vulnerable to the impacts of climate change, provides opportunities for improved planning and the development of cost-effective solutions to increase resiliency of infrastructure assets to these new weather patterns.

This report presents the results of the Climate Risk Assessment (CRA) study conducted for the Oneida Nation of the Thames housing assets using the First Nations PIEVC Protocol, a methodology adapted from Engineers Canada's Public Infrastructure Engineering Vulnerability Committee (PIEVC) Engineering Protocol [https://pievc.ca/protocol].

## 1.1 COMMUNITY DESCRIPTION

Oneida Nation of the Thames is a flourishing and vibrant Iroquois community<sup>1</sup>. The Oneida Nation of the Thames, like other Iroquois Nation's is a sovereign independent Nation with its own traditional hereditary and contemporary systems of governance and law. Established in 1840 as the "Oneida Settlement", it has transformed from an agricultural society into a modern and versatile Iroquois community.

The Oneida Nation of the Thames is home to 2,159 residents and has a total membership of 6,108. Located in picturesque southwestern Ontario, the Oneida Nation Settlement borders lush and fertile agricultural lands and is nestled along the eastern shore of the Thames River 30 kilometers south of the City of London.

<sup>&</sup>lt;sup>1</sup> Source: <u>https://oneida.on.ca/</u>

Introduction July 24, 2018



Figure 1: Satellite view of Oneida and surrounding area (Source: Google Earth).

The region has a humid continental climate influenced by its proximity to Lake Huron and regional elevation changes. Due to its continental location, the region experiences large seasonal contrasts with summers usually warm to hot and humid, with a July daily average temperature of 20.8 °C<sup>2</sup>. The region experiences frequent thunderstorms due to its summer weather and the convergence of air flows originating from Lake Huron and Lake Erie.

## 1.2 SCOPE OF THE STUDY

The objectives of the study are to:

- Identify infrastructure vulnerabilities to current and future severe weather. Oneida infrastructure considered in the study included the community's Senior's Complex, Standing Stone School and representative housing units.
- Establish a risk profile for the identified infrastructure.
- Provide recommendations regarding mitigating risks with the highest consequences to the assets, services, and community.

<sup>&</sup>lt;sup>2</sup> Source: <u>http://climate.weather.gc.ca/climate\_normals/results\_1981\_2010\_e.html?stnID=4789&autofwd=1</u>

Introduction July 24, 2018

### 1.3 PROJECT TIMELINE

Table 1 shows the timeline for the project.

### Table 1: Timeline for the Project

| Phase  | Completion Date                        |
|--|--|
| Start-up meeting                                       | August 2, 2017                         |
| Workshop 1: Define the project                         | September 19, 2017<br>October 26, 2017 |
| Workshop 2: Gather the data                            | October 26, 2017                       |
| Workshop 3: Complete the risk assessment               | November 16, 2017<br>December 8, 2017  |
| Request engineering analysis (optional)                | N/A                                    |
| Workshop 4: Prepare recommendations for action         | December 8, 2017<br>January 16, 2018   |
| Produce Climate Risk Assessment Report (this document) | July 24, 2018                          |

## 1.4 PROJECT TEAM

The Project Team included key staff from Oneida and Ontario First Nations Technical Services Corporation (OFNTSC) supported by subject matter experts from Stantec and Risk Sciences International (RSI). The members of the Project Team are listed below.

### Table 2. Project Team

| Project Team   |   |  |  |  |
|--|---|--|--|--|
| Oneida Nation of the Thames  | <u>OFNTSC</u>   |  |  |  |
| <ul> <li>H. Grant Doxtator, Councillor</li> <li>Chanda Kennedy, Band Administrator</li> <li>Jenelle Cornelius, Environmental Technologist</li> <li>Ron Elijah, I/Public Works Administrator</li> </ul> | Elmer Lickers, Senior O&M Advisor     Subject Matter Experts Support Team                       |  |  |  |
| Southern First Nations Secretariat (SFNS)  | <ul><li>Guy Félio, Senior Advisor (Stantec)</li><li>Heather Auld, Climatologist (RSI)</li></ul> |  |  |  |
| Randy Doxtator, Housing Advisor, Technical<br>Services   |   |  |  |  |

Step 1: Project Definition July 24, 2018

# 2.0 STEP 1: PROJECT DEFINITION

The Project Team met at Workshop 1 on September 19 2017 to define the project parameters; the validation and consensus on the project infrastructure was done prior to beginning Workshop 2 on October 26, 2017.

Following a presentation on the objectives of the project, an overview of the methodology for the climate risk assessment, and the Mohawk Council of Akwesasne Water/Wastewater Climate Risk Assessment project, the team discussed the assets to include in the study.

The Project Team decided to assess the climate (current and future) risks to Oneida's owned and operated housing

This first step of the Climate Risks Assessment (CRA) using the FN PIEVC Protocol involves setting the general boundary conditions for the project. The CRA project team identifies the infrastructure to be assessed and its key attributes, such as location, condition, known concerns, etc. The team identifies the overall climatic elements that affect the infrastructure and past weather events that have caused disruptions or failures to the service(s) provided by the asset(s).

assets: the Seniors Complex, quad-plex and duplex housing units, a representative single family dwelling and the Standing Stone School. The Project Team also included other infrastructure that provides services to these housing assets (water, wastewater and roads); however, the analysis of this additional infrastructure was done at a lower level of detail.

## 2.1 CLIMATE RELATED CONCERNS

Discussions focused on current concerns on meteorological events that have or are causing infrastructure and operations disruptions and/or failures, and on observations of changes in climate patterns. Following are the main points raised and discussed during Workshops 1 and 2.

- Snow storms mid to late 1970s; December 2007<sup>3</sup>
- Localized weather events intense short duration rains; strong wind gusts
- Wind damage in September and October 2017, increase in applications for wind damage repairs; reports of high winds and tree damage
- Tornado possibly in 1965; also in 1984 and 2009<sup>4</sup>

<sup>&</sup>lt;sup>3</sup> Information related to the December 2007 winter storm was found at

https://en.wikipedia.org/wiki/Early December 2007 North American winter storm <sup>4</sup> Information related to August 2009 tornadoes was found at

https://www.theweathernetwork.com/news/articles/southern-ontario-severe-storms-tornado-watch-devastatingtornadoes-storm/104590

Step 1: Project Definition July 24, 2018

• Ice storm - March 2007<sup>5</sup>; April 2018<sup>6</sup>

## 2.2 PHYSICAL ASSETS TO BE CONSIDERED

During Workshop 1 the goal was to identify the infrastructure components that will be considered in the assessment. During the Workshop, the Project Team listed the following preliminary infrastructure to be assessed.

- Seniors Complex
- Quad-plex
- Duplex
- Single family units (owned and maintained by the Oneida Nation Council; representative of the community's housing assets)
  - Additional support infrastructure at or near properties
    - Potable water
    - Wastewater treatment
    - Roads
    - Water Supply system
- Operations personnel
- Third-party services

In Workshop 2, the Project Team confirmed the asset list and decided to include to the assessment the Standing Stone School.

The community expressed concerns with activities occurring in areas neighbouring the Oneida Nation territory that have impacts on the infrastructure and are likely to be affected by future climate changes; they are:

- 1. Increased drainage volumes from neighbouring agricultural areas that flow on Oneida lands that have caused localized flooding; and
- 2. Potential climate change impacts on the City of Toronto Green Lane Landfill, East of Oneida (see Figure 1).

## 2.3 TIME HORIZON FOR THE STUDY

The time horizons for the study were selected as current conditions (establishing the baseline risks) and 2050s (2035 to 2065<sup>7</sup>) for future conditions. The future timeframe corresponds to the service life of many components of the assets being evaluated in this assessment.

<sup>&</sup>lt;sup>5</sup> Information related to the March 2007 storm was found at <u>https://ec.gc.ca/meteo-weather/default.asp?lang=En&n=53169766-1#r3</u>

<sup>&</sup>lt;sup>6</sup> Note this event was added at a later date than Workshops 1 and 2. Information found at: <u>https://globalnews.ca/news/4145554/ice-storm-ontario-weather-update/</u>

<sup>&</sup>lt;sup>7</sup> Climate is usually defined as the "average weather," or more rigorously, as the statistical description in terms of the mean and variability of meteorological variables such as temperature, precipitation and wind over a period of time, typically 30 years. (Source: World Meteorological Organization). The "2050s" projected climate is therefore the projected average over the 30-year period from 2035 to 2065.

Step 2: Data Collection July 24, 2018

# 3.0 STEP 2: DATA COLLECTION

## 3.1 INVENTORY OF INFRASTRUCTURE COMPONENTS

Information on the assets for this climate risk assessment was obtained from the staff of the Oneida Nation. It included relevant reports (e.g., the 2016 ACRS report<sup>8</sup>), policy<sup>9</sup> and planning documents, as well as information gathered during the workshops and a site visit. No inspections of the condition of the assets under consideration were conducted.

### 3.1.1 Oneida Senior Citizens Complex

The Oneida Seniors Complex is designed for people who are at least sixty (60) years of age or are living with a disability<sup>10</sup>. It is designed for those wishing to live independently and do not require full-time care providers. The rental units in the Oneida Seniors Complex are complete with all necessary appliances (including a fridge and stove). Heat, hydro, water, and sewage service are all provided for the tenants, as well as exterior and interior maintenance of the property and building common areas. The following images show different angles of the Complex and supporting infrastructure.



Figure 2. Front View of Entrance Senior Citizens Complex

<sup>&</sup>lt;sup>8</sup> Oneida Nation of the Thames, Asset Condition Report System report prepared by First Nations Engineering Services Ltd (October 2016)

<sup>&</sup>lt;sup>9</sup> Oneida Nation of the Thames, *Housing Policy – Procedures and Guidelines,* approved by Oneida Council, February 2015

<sup>&</sup>lt;sup>10</sup> Source: Oneida Nation of the Thames, *Housing Policy – Procedures and Guidelines,* approved by Oneida Council, February 2015

Step 2: Data Collection July 24, 2018



Figure 3. View of Front Individual Units of Senior Citizens Complex



Figure 4. Side View of Senior Citizens Complex with Propane Tanks

Step 2: Data Collection July 24, 2018



Figure 5. View of the Back Units of the Senior Citizens Complex



Figure 6. Back-up Generator at the Senior Citizens Complex

Step 2: Data Collection July 24, 2018

### 3.1.2 Quadplex

This four-unit housing complex is unique in Oneida. The Quaplex is serviced by community water and wastewater. The Oneida Council provides the tenants with heating; A/C, if desired, is the responsibility of the tenants.

The majority of the roof for the Quadplex is asphalt shingles; part of the roof was replaced with a metal roof in recent years as shown in Figures 8 and 9.



Figure 8. Rear View of Quadplex

Figure 7. Front View of Quadplex





Figure 9. Quadplex Roof: Metal and Asphalt Shingles

Step 2: Data Collection July 24, 2018

### 3.1.3 Duplex

This two-unit building is unique in Oneida. The Duplex is serviced by community water; wastewater is treated on-site. It has an asphalt shingles roof and vinyl siding.



Figure 10. Duplex: Angle View



Figure 11. Duplex: Side and Back View

Step 2: Data Collection July 24, 2018

### 3.1.4 Single Family Units

Figures 12 to 15 show examples of single dwelling units owned and maintained by the Oneida Council. The newer units (such as Unit #1 in Figure 12) have metal roofs, while the older (such as units #2, #3 and #4 respectively in Figures 13 to 15) have asphalt shingles roofs. All Oneida Council housing units are serviced by community water; some are connected to the community wastewater collection system, others have on-site treatment. Most units use propane as fuel for heating.



Figure 12. Single Family Unit #1

Figure 13. Single Family Unit #2



Step 2: Data Collection July 24, 2018



Figure 14. Single Family Unit #3



Figure 15. Single Family Unit #4

### 3.1.5 Standing Stone School

Standing Stone School is a community Junior Kindergarten to Grade 6 elementary school serving approximately 210 students<sup>11</sup>. It was built in 1976 and an addition constructed in 1997.

The Standing Stone School consists of a combination of concrete block and steel frame construction<sup>12</sup>. The foundation is poured concrete walls and footings. The roof is a combination of a multi-level flat roof system and some sloped metal roof sections. Approximately half of the roof was reconstructed in 2013. The exterior walls are brick veneer. The flooring is mainly vinyl tiles, there is a combination of painted concrete block and painted gypsum board interior walls and a combination of acoustical ceiling tiles and painted gypsum board ceilings. The heating is provided by propane fired boilers, while the cooling is provided by a cooling tower system. The lighting is mainly fluorescent units.

<sup>&</sup>lt;sup>11</sup> Source: https://oneida.on.ca/standing-stone-school/

<sup>&</sup>lt;sup>12</sup> Source: Oneida Nation of the Thames, *Asset Condition Report System* report prepared by First Nations Engineering Services Ltd (October 2016)

Step 2: Data Collection July 24, 2018

The Standing Stone School is protected by a security alarm, a fire alarm and by a video surveillance system. It is equipped with fire extinguishers and emergency lighting.

The School water is supplied via a piped water system. Wastewater is treated on-site.

Contraction of the second seco

Figure 16: Standing Stone School Entrance (Source: https://oneida.on.ca/standing-stone-school/)



Figure 17. Satellite View of Standing Stone School (Source: Google Earth)


Step 2: Data Collection July 24, 2018


### 3.2 CONDITION OF INFRASTRUCTURE COMPONENTS

In terms of condition/performance rating, no field inspection was carried out by the Project Team. The condition and performance of the assets was exclusively based the ACRS inspection report (2016) for INAC funded assets, as well as information gathered during a site visit (exterior only) and from the Oneida staff on the Project Team.

## 3.3 CLIMATE CONSIDERATIONS

The general temperature and precipitation annual average profile for the closest Environment Canada weather station (St Thomas WPCP, Station ID 6137362) is shown in Figure 18 below.





Climate elements were part of the discussions at each of the four workshops of the project. In Workshop 1, participants were asked to recall weather events that may have caused damage/disruptions to the selected infrastructure. During Workshops 2 and 3, the Project Team members reviewed the list of weather elements suggested by the FN PIEVC Protocol and selected those relevant to the infrastructure under assessment and local/regional climate conditions.

The climate considerations presented are the result of discussions among team members at the project workshops, research into public information and news reports, and the following reports:

• Climate change projections for Ontario: An updated synthesis report for policymakers and planners. Ontario Ministry of Natural Resources and Forestry, Climate Change Research Report CCRR-44, 2015

Step 2: Data Collection July 24, 2018

• *City of London: Vulnerability of Infrastructure to Climate Change*, Water Resources Research Report by A. Peck et al., University of Western Ontario, 2011

The selection of climate parameters and infrastructure thresholds was the result of the workshops during which the history of infrastructure-weather interactions that have caused structural or functional failures, or service disruptions were discussed.

### 3.3.1 Climate Trends and Projections

The main source of climate data was the Environment Canada weather station at St Thomas WPCP (Station ID: 6137362)

The figures below provide examples of data used for the study; details are provided in the Workshop presentations in Appendix A. Future climate projections were based on the Intergovernmental Panel on Climate Change (IPCC) RCP<sup>13</sup> 4.5 scenario - a stabilization scenario in which total radiative forcing is stabilized shortly after 2100<sup>14</sup>.

Mean daily temperatures have been increasing over the past 60-plus years as shown in Figure 19 and Figure 20. These figures also show that under the RCP 4.5 scenario, temperatures are projected to continue increasing over the next 30 years. The IPCC is the international body for assessing the science related to climate change. The IPCC was set up in 1988 by the World Meteorological Organization (WMO) and United Nations Environment Programme (UNEP) to provide policymakers with regular assessments of the scientific basis of climate change, its impacts and future risks, and options for adaptation and mitigation.

IPCC assessments provide a scientific basis for governments at all levels to develop climate related policies, and they underlie negotiations at the UN Climate Conference – the United Nations Framework Convention on Climate Change (UNFCCC). The assessments are policy-relevant but not policy-prescriptive: they may present projections of future climate change based on different scenarios and the risks that climate change poses and discuss the implications of response options, but they do not tell policymakers what actions to take.

On average, Summer precipitation has shown no significant increase or decrease and this trend is projected to continue as shown in Figure 21. Total Winter precipitation has increased over the past 60-plus years, and models project a continuing increase in the future (Figure 22).

Winter rain is of particular interest since it occurs when the ground is frozen and thus stormwater catchment systems may be blocked by snow and ice. For Southern Ontario, the threshold for a weather warning causing flood is a 25 mm rainfall. Figure 23 shows the historical records of 3/5/7 consecutive days of winter rain; from 1980 to 2017, a winter rain greater than 25mm over a 3-day period has occurred almost every year.

<sup>&</sup>lt;sup>13</sup> RCP: Representative Concentration Pathways – a greenhouse gas concentration (not emissions) trajectories adopted by the Intergovernmental Panel on Climate Change (IPCC) for its fifth Assessment Report (AR5) in 2014.

<sup>&</sup>lt;sup>14</sup> By comparison, RCP 8.5 is characterized by increasing greenhouse gas emissions over time, representative of scenarios in the literature that lead to high greenhouse gas concentration levels, while RCP 2.6 emission pathway is representative of scenarios that lead to very low greenhouse gas concentration levels.

Step 2: Data Collection July 24, 2018




Figure 19. Mean Daily Temperature for Summer - Historical Trend and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)




Figure 20. Mean Daily Temperature for Winter - Historical Trend and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)

Step 2: Data Collection July 24, 2018




Figure 21. Summer Precipitation - Historical Trend and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)





Figure 22. Winter Precipitation - Historical Trend and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)

Step 2: Data Collection July 24, 2018



#### Figure 23. Winter Rain Events

Tables 3 and 4 below present historical and projected rainfall intensity, duration and frequency (IDF) data. Rainfall IDF information is used, for example, in stormwater management design. The information presented in Tables 3 and 4 are for the St. Thomas weather station; the data was obtained from the University of Western Ontario Institute for Catastrophic Loss Reduction (ICLR) Computerized Tool for the Development of Intensity-Duration-Frequency Curves under Climate Change – Version 3.0 at <a href="http://www.idf-cc-uwo.ca/">http://www.idf-cc-uwo.ca/</a>.

| T<br>(years) | 2     | 5     | 10    | 25    | 50     | 100    |
|--------------|-------|-------|-------|-------|--------|--------|
| 5 min        | 8.25  | 11.02 | 13.04 | 15.82 | 18.07  | 20.47  |
| 10 min       | 12.26 | 16.28 | 18.85 | 22    | 24.28  | 26.47  |
| 15 min       | 14.87 | 19.91 | 23.13 | 27.08 | 29.92  | 32.67  |
| 30 min       | 20.12 | 26.99 | 31.48 | 37.1  | 41.21  | 45.27  |
| 1 h          | 25.59 | 34.75 | 40.58 | 47.69 | 52.79  | 57.71  |
| 2 h          | 29.7  | 41.19 | 49.44 | 60.65 | 69.58  | 78.99  |
| 6 h          | 37.78 | 51.28 | 61.63 | 76.58 | 89.2   | 103.19 |
| 12 h         | 43.67 | 58.81 | 69.82 | 84.95 | 97.14  | 110.11 |
| 24 h         | 49.29 | 66.81 | 79.34 | 96.31 | 109.77 | 123.92 |

#### Table 3. Historical IDF - Accumulated Precipitation (mm)

Step 2: Data Collection July 24, 2018

| T<br>(years) | 2     | 5     | 10     | 25     | 50     | 100    |
|--------------|-------|-------|--------|--------|--------|--------|
| 5 min        | 10.14 | 14.13 | 16.78  | 21.22  | 24.59  | 28.23  |
| 10 min       | 15.04 | 20.88 | 24.22  | 29.82  | 33.58  | 37.37  |
| 15 min       | 18.25 | 25.53 | 29.71  | 36.69  | 41.4   | 46.13  |
| 30 min       | 24.7  | 34.62 | 40.45  | 50.19  | 56.9   | 63.71  |
| 1 h          | 31.41 | 44.56 | 52.1   | 64.66  | 73.12  | 81.6   |
| 2 h          | 36.52 | 52.81 | 63.54  | 81.39  | 94.89  | 109.37 |
| 6 h          | 46.48 | 65.76 | 80.55  | 102.24 | 120.39 | 140.67 |
| 12 h         | 53.69 | 75.44 | 89.84  | 113.93 | 132.24 | 151.97 |
| 24 h         | 60.59 | 85.66 | 102.05 | 129.34 | 149.8  | 171.66 |

#### Table 4. Projected 2050s IDF (2025 - 2075 average) – Accumulated Precipitation (mm)

The Tables show that for the 1:100 return period rainfalls, the future projected accumulated rainfall will increases ranging from 36.3% (6-hour rainfall) to 41.4% (1-hour event), with an average increase of 19.3% for all 1:100 rainfalls. The data in Tables 3 and 4 can also be used to establish the increased frequency of particular rainfall events. For example, the current climate 1:100 year, 24hr rainfall is project to have a return period of less than 25 years.

Figures 24 and 25 show the current and projected cooling and heating degree days respectively. A cooling [heating] degree day is a measurement that quantifies the demand for energy needed to cool [heat] a building; it is the number of degrees that a day's average temperature is above [below] 18° Celsius, which is the temperature above [below] which buildings need to be cooled [heated].




Figure 24. Cooling Degree Days - Current and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)

Step 2: Data Collection July 24, 2018




Figure 25. Heating Degree Days - Current and Future Climate Projection (St. Thomas Weather Station, RCP 4.5)

Figure 26 below shows there have been more than 40 tornadoes on record within a 50-km radius of the St. Thomas weather station. The Oneida Nation of the Thames has not experienced a tornado within its community, but is located in South-West Ontario's "Tornado Alley".




Figure 26. Tornado Records within 50km of St. Thomas

3.15

Step 2: Data Collection July 24, 2018

### 3.3.2 Climate Elements Considered to Affect the Infrastructure


The selected climate elements for the exposure, vulnerability, and risk assessments are shown in Table 5 below. They were selected by the Project Team as representative of events that have caused or are likely to cause structural, operational or functional disruptions or failures to the infrastructure considered in this study.

| Type of Climate<br>Element | Description                              | Comment  |  |
|----------------------------|--|--|--|
| Temperature                | Extreme High Temperatures                | Days (per year) with Max Temps > 36°C                                    |  |
|                            | High Temperatures                        | Occurrences of days with temperature greater than 30°C (10 or more days) |  |
|                            | Seasonal temperature variations          | Heating and cooling degree days  |  |
| Precipitation              | Short duration - High Intensity rainfall | 50mm in 30 minutes   |  |
|                            |  | Type of rainfall that has caused localized flooding in the community     |  |
|                            | Freezing rain                            | Estimated 15 mm causing local power line damage                          |  |
|                            | 3 consecutive days of winter rain        | Southern Ontario Threshold for weather warning causing flood of 25 mm    |  |
| Winds                      | Exceeding 100 km/h                       | Damage to asphalt shingle roofs, trees and power lines                   |  |
|                            |  | 5 events with wind gusts > 100km/h in London (ON) between 1981 and 2010  |  |
|                            | Tornado                                  |  |  |

Table 5: Principal Climate Elements Selected by the Project Team for the Analysis

Step 3: Risk Assessment July 24, 2018

# 4.0 STEP 3: RISK ASSESSMENT



Step 3 of the FN PIEVC Protocol instructs the Project Team to perform the following steps, illustrated in Figure 27.

Figure 27: FN PIEVC Protocol Risk Assessment Process Flowchart

### 4.1 **RISK THRESHOLDS**

**Risk** is defined as the product of the **Probability** score multiplied by the **Severity** score. Since the probability and the severity scores are each rated from 0 to 5, the maximum risk score will be 25 as illustrated below. For this project, the Project Team selected the risk thresholds shown in Table 6 below.

| r                |  |
|------------------|--|
| Score            | Description  |
| < 5              | Low: No action required  |
| 6 to 14          | <b>Moderate:</b> Monitoring recommended; action may be required if threat materialises; a more detailed analysis may be needed   |
| ≥ 15             | <b>Hight:</b> Action required; immediate attention if risk occurs in current climate; adaptation planning necessary if risk occurs in future climate projections       |
| Special<br>Cases | <ul> <li>Frequently recurring events, low single event impacts but accumulated effects</li> <li>Low probability, high impact events (for example, tornados)</li> </ul> |

#### **Table 6: Risk Thresholds**

Step 3: Risk Assessment July 24, 2018

## 4.2 INFRASTRUCTURE RESPONSE

During Workshop 2, the Project Team members selected the infrastructure response criteria against which the infrastructure-climate interactions and risks would be evaluated. The reader is encouraged to study the details of the infrastructure responses selected in Workshop 3, that are provided in Appendix A. They are summarized below:

Infrastructure response:

- 1. Structural capacity
- 2. Functionality
- 3. Operations, maintenance, and materials performance

Community impacts:

- 1. Emergency response
- 2. Insurance and legal considerations
- 3. Policy considerations
- 4. Social and cultural effects
- 5. Impacts on the environment
- 6. Financial/fiscal impacts

## 4.3 CLIMATE PROBABILITY SCORING

The FN PIEVC Protocol rates the probability of the climate events occurring (current and future climate) as follows:

| Score | Description                   |  |
|-------|-------------------------------|--|
| 0     | Negligible<br>Not applicable  |  |
| 1     | Highly unlikely<br>Improbable |  |
| 2     | Remotely possible             |  |
| 3     | Possible<br>Occasional        |  |
| 4     | Somewhat likely<br>Normal     |  |
| 5     | Likely<br>Frequent            |  |

### Table 7: FN PIEVC Probability Scoring

The following table presents the results of the climate analysis (current trends and future projections), and the corresponding FN PIEVC probability scores used in the risk assessment. The scores were produced by the Protect Team considering climate trends and future projections, individual knowledge and experience of past events, and news records of events that caused infrastructure damage in the area.

Step 3: Risk Assessment July 24, 2018

### **Table 8: Probability Scores for Selected Climate Events**

| Type of<br>Climate | Description                              | Comment   | Rating             |                   |
|--------------------|--|---|--------------------|-------------------|
| Element            |  |   | Current<br>Climate | Future<br>Climate |
| Temperature        | Extreme High Temperatures                | Days (per year) with Max Temp.<br>>36°C (Current climate average =<br>0.1 days/year)  | 2                  | 3                 |
|                    | High Temperatures                        | Occurrence of 10 days/year with<br>Temp. >30°C. (Current climate<br>average = 8.7 days/year)  | 4                  | 5                 |
|                    | Seasonal temperature variations          | Heating and cooling degree days<br>(Current climate: cooling 293 days)  | 4                  | 5                 |
| Precipitation      | Short duration - High Intensity rainfall | 50mm in 30 minutes: Corresponds<br>approximately to a 1:100 year event<br>Type of rainfall that has caused<br>localized flooding in the community –<br>projected to occur more often (1:30<br>year event or less) | 2                  | 4                 |
|                    | Freezing rain                            | Estimated 15 mm causing local<br>power line damage  | 3                  | 4                 |
|                    | 3 consecutive days of winter rain        | Southern Ontario Threshold for<br>weather warning causing flood of 25<br>mm<br>Has occurred 26 times in last 30<br>years (St. Thomas station; 1 year<br>missing data)   | 4                  | 5                 |
| Winds              | Exceeding 100 km/h                       | Damage to asphalt shingle roofs,<br>trees and power lines<br>5 events with wind gusts > 100km/h<br>in London (ON) between 1981 and<br>2010. Source Environment Canada <sup>15</sup>                               | 3                  | 4                 |
|                    | Tornado                                  | 40 Tornadoes on record within 50km<br>of Oneida. Difficult to project whether<br>the number and intensity of tornados<br>will increase or decrease in the future  | 2                  | N/A               |

15

http://climate.weather.gc.ca/climate\_normals/results\_1981\_2010\_e.html?searchType=stnName&txtStationName=lon don&searchMethod=contains&txtCentralLatMin=0&txtCentralLatSec=0&txtCentralLongMin=0&txtCentralLongSec=0& stnID=4789&dispBack=1

Step 3: Risk Assessment July 24, 2018

## 4.4 INFRASTRUCTURE SEVERITY SCORING

The following rating system was used for the assessment of the severity of impacts on the infrastructure should a selected climate event occur. Figure 28 below shows a photo of the Project Team having completed the Infrastructure Severity Scoring.



Figure 28. Photo to Project Team having completed the Infrastructure Severity Scoring table at Workshop 3 on November 16, 2017 (Photo by Guy Félio)

Step 3: Risk Assessment July 24, 2018

| Score and<br>Description | Consequence [Structural, Functional, Operations]  |
|--------------------------|---|
| 0<br>No effect           | <ul> <li>No damage</li> <li>Continues to perform as intended</li> <li>Fully operational – normal</li> </ul>   |
| 1<br>Insignificant       | Can be corrected through the regular maintenance cycle  |
| 2<br>Minor               | <ul> <li>Requires sending repair crew</li> <li>No replacement of asset necessary</li> <li>May need further assessment</li> </ul>  |
| 3<br>Moderate            | <ul> <li>Needs attention</li> <li>Requires sending repair crew</li> <li>Needs replacement of components</li> <li>Might need to order parts</li> <li>Will need further assessment</li> </ul>   |
| 4<br>Major               | <ul> <li>Collapse/total loss of asset or components</li> <li>Little or no impacts on other elements</li> </ul>  |
| 5<br>Catastrophic        | <ul> <li>Collapse</li> <li>Total loss of equipment and service that requires full replacement of asset, several assets and major components</li> <li>Will require relocating people/function</li> <li>Impacts on other elements of asset or other assets</li> <li>May have impacts on the public health and safety</li> </ul> |

### Table 9: Infrastructure Severity Scoring Developed by the Project Team

## 4.5 RISK ASSESSMENT

This section of the report presents the infrastructure components that were evaluated, describes the risk screening process, summarizes the results of the risk assessment, and discusses the influence of the infrastructure condition on the risk assessment.

### 4.5.1 Infrastructure Components Evaluated

The infrastructure assets considered in this assessment were divided into components to evaluate the impacts from the selected climate events. Table 10 shows the detailed lists of assets/components.

The Green Lane landfill and adjacent communities' activities (agricultural areas bordering the Oneida Nation of the Thames community) were included in the list of infrastructure that can potentially be impacted by current or future weather extremes, which may result in impacts on the Oneida community. The Project Team understands these

Step 3: Risk Assessment July 24, 2018

infrastructures are not controlled by the Oneida Nation, but felt including them in the assessment would be useful to initiate discussions with relevant stakeholders to address potential impacts on the community.

#### **Table 10: Infrastructure Assessed**

| Seniors Complex (16 units) | Duplex                  | School                            |  |  |
|----------------------------|-------------------------|-----------------------------------|--|--|
| Building envelope          | Building envelope       | Building envelope                 |  |  |
| Building structure         | Building structure      | Building structure                |  |  |
| Roof                       | Roof                    | Roof                              |  |  |
| Foundations                | Foundations             | Roof equipment                    |  |  |
| Heating/Cooling            | Heating/Cooling         | Foundations                       |  |  |
| Fuel (propane)             | Fuel                    | Heating/Cooling                   |  |  |
| Access roads               | Roads                   | Fuel (propane)                    |  |  |
| Backup generator           | Drainage                | Access road                       |  |  |
| Wastewater treatment       | Wastewater treatment    | Wastewater treatment              |  |  |
| Quadplex                   | Single family dwellings | Services                          |  |  |
| Building envelope          | Building envelope       | Electricity                       |  |  |
| Building structure         | Building structure      | Water                             |  |  |
| Roof                       | Roof (asphalt shingles) | Community Wastewater<br>treatment |  |  |
| Foundations                | Roof (steel)            | Propane supplier                  |  |  |
| Heating/Cooling            | Foundations             |                                   |  |  |
| Fuel                       | Heating/Cooling         | Diesel supplier                   |  |  |
| Roads                      | Fuel                    | Operations personnel              |  |  |
| Drainage                   | Roads                   | Regional Landfill (Green Lane)    |  |  |
| Wastewater treatment (On-  | Drainage                | Adjacent communities'             |  |  |
| site)                      | Wastewater treatment    | activities                        |  |  |
|                            |                         | Agriculture drainage              |  |  |

### 4.5.2 Risk Screening Process

The first step in the production of the risk matrix (steps illustrated in Figure 18) is to evaluate whether there is an interaction between an infrastructure component and a climate event, also referred to as establishing the exposure of the infrastructure to the climate hazards. Where an interaction exists, the Project Team identifies with respect to which infrastructure performance considerations the potential risk might exist (e.g. impacts on the structural capacity or the functionality of the asset or component) - see Section 4.2 of this report for a description of the infrastructure performance considerations study.

### 4.5.3 Summary of Risk Results

Table 11 presents a summary of the risk counts for the number of infrastructure-climate interactions in each risk threshold category (Moderate, and High). The table also presents the infrastructure assets or components affected, and the performance impacted if the risks occur. The general risk matrices created for this project consider

Step 3: Risk Assessment July 24, 2018

infrastructure in a good state of repair, operating at the performance level for which it was designed. Finally, the risk summary only considers the infrastructure that is owned and maintained by the Oneida Council, or its supplier. The impacts of the Green Lane Landfill and adjacent lands' agricultural activities, and the risks associated with tornadoes are not included in the table.

The highest risks to the infrastructure and community identified by the study are:

- 1. **Observed and projected strong winds:** they impact asphalt shingle roofs, vinyl siding, tree branches and power lines. Strong winds have caused damages to different assets in the past and are projected to increase in intensity and frequency. These winds can also blow debris, light equipment or material in yards that is not tied down, creating risks of damage to property and safety concerns to people.
- 2. Short duration, high intensity rainfall events: the selected threshold (rainfall of 50mm in 30 minutes) has caused localized flooding in the community in the past. Projections show that this type of event will happen more often, and more intensely in the future. Short duration, high intensity rainfall can cause road flooding, overflowing of drainage ditches, carry debris that block culverts, flood septic beds, etc.
- 3. Freezing rain: freezing rain of 15mm or more is currently common in Oneida, and projected to occur more often. Direct damage to trees and power-lines can occur due to ice accumulation. Freezing rain can impact personnel travelling on foot or in vehicles, as well as the tools they use and the equipment they are sent to maintain or repair. Freezing rain requires immediate attention to ensure the safety of the public on roads, parking lots and entrances to public buildings.

The results show a slight increase in Moderate risks from current climate to the 2050s (54 to 57) but a substantial increase (16 to 37) in High risks. This is mainly due to projected future increases in the number of days with temperatures greater than 36°C, the change in seasonal temperatures (increased cooling requirements), and the rise in rainfall events (short duration/high intensity and consecutive days with rain).

Step 3: Risk Assessment July 24, 2018

#### Table 11: Summary of Moderate and High Risks

| F                             | Risk Score C       | ounts                     |  |  |
|-------------------------------|--------------------|---------------------------|--|--|
| Risk<br>Threshold<br>Category | Current<br>Climate | Future (2050s)<br>Climate | Main Climate Events                                  | Principal Infrastructure Affected  |
| Moderate                      | 54                 | 57                        | Maximum temperatures and seasonal changes            | <ul><li>Heating and cooling systems in buildings</li><li>Operations personnel</li></ul>  |
|                               |                    |                           | Freezing rain  | <ul> <li>Buildings (envelope, roof, surface and external equipment)</li> <li>Third party services (electricity, fuel suppliers)</li> </ul> |
|                               |                    |                           | Precipitation (Rain) – short duration/high intensity | <ul><li>Access roads and drainage</li><li>On-site sewage treatment</li></ul>   |
|                               |                    |                           | <ul> <li>Strong winds (&gt; 100 km/h)</li> </ul>     | <ul> <li>Roofs and roof mounted equipment</li> <li>Trees and power lines</li> <li>Buildings (envelope and structure)</li> </ul>            |
| High                          | 16                 | 37                        | Maximum temperatures and seasonal changes            | <ul><li>Heating and cooling systems in buildings</li><li>Operations personnel</li></ul>  |
|                               |                    |                           | Freezing rain  | <ul> <li>Buildings (envelope, roof, surface and external equipment)</li> <li>Third party services (electricity, fuel suppliers)</li> </ul> |
|                               |                    |                           | Precipitation (Rain) – short duration/high intensity | <ul><li>Access roads and drainage</li><li>On-site sewage treatment</li></ul>   |
|                               |                    |                           | Precipitation (Winter rain)                          | <ul><li>Access roads and drainage</li><li>On-site sewage treatment</li></ul>   |
|                               |                    |                           | • Strong winds (> 100 km/h)                          | <ul> <li>Roofs and roof mounted equipment</li> <li>Trees and power lines</li> <li>Buildings (envelope and structure)</li> </ul>            |

Step 3: Risk Assessment July 24, 2018

### 4.6 COMMUNITY IMPACTS FROM INFRASTRUCTURE RISKS

Infrastructure loss of performance or function affects the whole community. Resilient infrastructure is necessary to provide resilient services that, in turn, contribute to the resilience of the community. The community impacts selected for this study are as follows:

- 1. Emergency response services can be impacted in following manners:
  - a. Increased demand due to higher number of emergencies or broad area covered by the event;
  - b. Impacts to the facilities, equipment and personnel that are used to provide emergency services; and
  - c. Loss of functionality of roads or other routes to access the locations where emergencies occur
- Insurance and legal impacts may result from a failure in the services or damages from the collapse of public assets. For example: basement flooding due to loss of stormwater system capacity; fallen public trees on private property; failure of wastewater systems resulting in temporary facilities' closures or environmental damage; etc.
- Policy considerations relate to the processes, procedures and guidelines that affect the performance of the infrastructure in providing services. As indicated in the previous section, maintaining and operating the infrastructure in a state of good repair and re-capitalizing the assets in a timely manner can be part of a risk mitigation strategy.
- 4. **Social and cultural effects** result from the loss of services provided by the infrastructure. In the particular case of water and wastewater services, the impacts are multiple and varied, and can range from mere inconvenience to health and safety issues. These will compound to the hardships experienced by the community in the event of extreme climate events.
- 5. **Environmental impacts** may result in short or long-term stress to the community, for example, in the event of the loss of key environmental features on a temporary or permanent basis.
- Financial impacts may redirect resources from other planned investments or priority areas in the community. With limited sources of funding available, the Oneida Council may have to take extraordinary measures to address its financial situation. This could be in the form, for example, of lowering levels of services.

Conclusions and Recommendations July 24, 2018

## 5.0 CONCLUSIONS AND RECOMMENDATIONS

Infrastructure in a community exists to provide a service. Since many of the components or assets within infrastructure systems have long service lives, there are many opportunities to introduce climate change adaptation measures throughout this life-cycle.

The housing assets, school and infrastructure that provides services of the Oneida Nation of the Thames are generally well maintained and provide safe services to the community; details are beyond the scope of this assessment but can be found in past recent inspection reports. The Oneida Council, under budget pressures, has managed to maintain these assets in a state of good repair; the maintenance practices they have adopted and implemented have resulted in resilient infrastructure.

The Project Team identified adaptive and risk mitigation measures during Workshop 4. Since the intent of the study is to provide an overall risk profile of the assets owned and managed by the Oneida Council, the recommendations do not address specific infrastructure issues. The recommendations in Table 12 below are not listed in a priority order.

#### Tornadoes

The Oneida community is located in Southwest Ontario's "Tornado Alley" and there have been more than 40 tornadoes on record within a 50km radius of St Thomas. This type of devastating weather event has not affected the Oneida community; however, the Project Team discussed possible risk prevention and mitigation measures against tornadoes, as follows (please note some of these recommendations also apply to strong wind events):

- 1. Work with the local radio station to develop a tornado warning and alert system; this could also use social media and local mobile phone services.
- 2. Review the Community Emergency Plan, possibly updating it considering the results of this climate risks assessment. Communicate relevant sections of the Plan to affected departments and stakeholder.
- 3. Since 2015, the Oneida Council requires that all new residential construction use metal roofs a measure that this climate risks assessment confirms has merit to protect community housing and other building assets. The Oneida Council is currently also considering making mandatory the use of hurricane ties<sup>16</sup> (straps) in new construction.
- 4. Property maintenance: ensure loose material is removed from areas around the assets, and that external light equipment susceptible to strong winds is tied-down. The Project Team suggested a Council Housing Policy for inspections of the properties every 2 years and creating a database to track potential hazards.

#### Adjacent Communities' Activities

Concerns regarding increased runoff and drainage discharges affecting the Oneida community were discussed throughout this climate risks assessment. Oneida staff mentioned the increase in outfall drainage pipe sizes from

<sup>&</sup>lt;sup>16</sup> See related article: <u>https://www.insuranceinstitute.ca/en/cipsociety/Articles/Items/2017/10/16/ICLR-researching-wind-damage-on-partiallybuilt-wood-framed-structures</u>

Conclusions and Recommendations July 24, 2018

neighbouring agricultural operations which they believe has two negative impacts on the community: 1) increase in potential deleterious substances into the Thames river, and 2) potential flooding of community lands.

Addressing climate risks associated with adjacent community lands and operations is beyond the scope of this assessment. However, in view of the projected increased in precipitation intensity in future climate, this study provides the opportunity to initiate discussions with stakeholders and authorities to mitigate these risks. A review of constructed drains<sup>17</sup> could be performed to establish if improvements can be made to protect the Oneida Nation of the Thames lands.

#### Green Lane Landfill

The concerns the Oneida Council has with the operations of the Landfill have historically been with odour and rodents (for example, see: <a href="https://www.cbc.ca/news/canada/london/green-lane-landfill-oneida-nation-smells-1.4567724">https://www.cbc.ca/news/canada/london/green-lane-landfill-oneida-nation-smells-1.4567724</a> ). Assessing the climate risks at the Landfill and its potential impacts on the Oneida community was not part of the study. However, in view of the projected climate changes identified, this study provides the opportunity to initiate discussions with the Landfill owner and operator to identify and mitigate as required potential risks to the Oneida community.

| Climate Event        | Risk Mitigation and Adaptation Measures  |
|----------------------|--|
| Maximum temperatures | <ul> <li>Senior Citizens Complex</li> <li>A/C is only provided in common areas (some tenants have their own A/C units in their quarters) – in the event of central A/C capacity problems, consider rotating cooling areas in the Complex.</li> <li>Check and adjust as necessary, based on projected future climate, the capacity and specification of the A/C system at the time of retrofit or major repairs.</li> <li>Inform residents about heat waves and extreme temperatures; prepare measures to help residents remain cool and hydrated.</li> <li>Housing units</li> <li>Explore costs and benefits to install A/C in existing furnaces for projected future temperature increases. This would also improve the indoor air quality.</li> <li>Develop a "Home Owners Manual" guide to educate and help tenants and property owners with best practices to deal with current extreme weather and project future climate extremes, for example: cleaning the propane exhaust pipes to prevent air quality issues in the house.</li> <li>Other infrastructure</li> <li>Water demand during high temperature periods increases which may result in supply risks (for example, aquifer drawdown). Consider water conservation measures including a public education campaign on the importance of conserving water during these periods.</li> <li>Explore arrangements with neighbouring communities for emergency water supply in cases of low water supply.</li> <li>Work with local and regional authorities, industry (for example, golf courses) and stakeholders to protect the raw water sources (river and aquifer) during periods of drought and high temperatures.</li> </ul> |

#### Table 12. Risk Mitigation and Adaptation Measures recommendations


<sup>&</sup>lt;sup>17</sup> See: <u>http://www.omafra.gov.on.ca/english/landuse/gis/condrain.htm</u>

Conclusions and Recommendations July 24, 2018


| Climate Event   | Risk Mitigation and Adaptation Measures  |
|---|--|
| Rain (short duration, high intensity)   | <ul> <li>Housing <ul> <li>Explore gravity-fed sump pumps in case of power failures. Communicate benefits to the public; explore working with suppliers.</li> <li>Explore slab-on-grade construction to avoid basement flooding risks due to rain events and the high groundwater levels in the area.</li> </ul> </li> <li>School (recommendations also applies to winter rain) <ul> <li>Maintain the drainage system of the flat roof free of debris. Inspect after each severe weather event.</li> <li>Assess the capacity of the roof drainage system based on the current severe and projected more intense future rainfall events.</li> </ul> </li> </ul>  |
| <ul> <li>each severe weather event.</li> <li>Assess the capacity of the roof drainage system based on the severe and projected more intense future rainfall events.</li> <li>Inspect and possibly replace the old septic system.</li> </ul> Rain (consecutive days of vinter rain) <ul> <li>Drainage</li> <li>Ensure drainage system (ditches, culverts) is clear of debris ar performs at its design capacity.</li> <li>Conduct a stormwater management study to assess the draina system capacity under current and projected future climate cor</li> </ul> Freezing Rain <ul> <li>Buildings</li> <li>Inspect after freezing rain events.</li> <li>Clear debris and branches that can pose safety hazards.</li> <li>Use environmentally friendly de-icing salts around the Senior C complex, the school and administration buildings to reduce dar concrete and other materials.</li> </ul> | <ul> <li>Drainage</li> <li>Ensure drainage system (ditches, culverts) is clear of debris and performs at its design capacity.</li> <li>Conduct a stormwater management study to assess the drainage</li> </ul>   |
| Freezing Rain   | <ul> <li>Buildings <ul> <li>Inspect after freezing rain events.</li> <li>Clear debris and branches that can pose safety hazards.</li> <li>Use environmentally friendly de-icing salts around the Senior Citizens complex, the school and administration buildings to reduce damage to concrete and other materials.</li> </ul> </li> <li>Personnel: <ul> <li>Provide personnel with proper safety equipment.</li> <li>Apply sand and salt in working areas.</li> <li>Train/refresh training staff in safe operating practices.</li> </ul> </li> <li>Third party services <ul> <li>Include potential loss of service in emergency planning.</li> </ul> </li> <li>Back-up electricity <ul> <li>Ensure portable back-up generators are available for essential services in case of power failure.</li> <li>Maintain backup generators including fuel conditioning to ensure service when required.</li> </ul> </li> </ul> |
| Wind  | <ul> <li>Buildings:</li> <li>Continue requirement of metal roofs for new residential construction.</li> <li>Implement policies to protect housing against strong wind events, such as requiring hurricane ties in all new construction.</li> </ul>   |

Appendix A Workshop Presentations July 24, 2018

## Appendix A WORKSHOP PRESENTATIONS








| Time              | Description   |   |  |
|-------------------|---|---|--|
| 9:30am – 9:45am   | Welcome and introductions   | Oneida Nation of the<br>Thames and OFNTSC |  |
| 9:45am – 10:45am  | Description of the FN PIEVC vulnerability assessment process                          | Stantec                                   |  |
| 10:45am – 11:00am | Health break  |   |  |
| 11:00am – 12:00am | Description of Oneida housing assets and related infrastructure and WW                | Oneida Nation of the Thames               |  |
| 12:00pm – 12:30pm | Discussion: current / future housing<br>assets and related infrastructure<br>concerns | All participants                          |  |
| 12:30pm – 1:15pm  | Lunch   |   |  |





# Workshop #1 - Agenda


| Time            | Description   |                  |           |
|-----------------|---|------------------|-----------|
| 1:15pm – 2:15pm | Facilitated discussion: selection of the<br>assets and related infrastructure for<br>vulnerability assessment           | All participants |           |
| 2:15pm – 3:15pm | Presentation on climate trends and future climate projections   | Stantec          |           |
| 3:15pm – 3:30pm | Health Break  |                  |           |
| 3:30pm – 4:15pm | Discussion: past climate events that have caused disruptions or damage to the housing assets and related infrastructure | All participants |           |
| 4:15pm – 4:45pm | Roles and responsibilities of the team<br>members<br>Next steps.  |                  |           |
| 4:45pm          | Adjourn   |                  |           |
|                 |   |                  | 🚺 Stantec |

























# Akwesasne W/WW Climate Change Vulnerability Assessment Objectives

- Identify **nature and severity of risks to components in a life-cycle context** – compatible with asset management plans
- **High level assessment of the predominant vulnerabilities** to climate change and optimize more detailed engineering analysis
- **Recommendations** for adjustments to design, operations and maintenance to maintain / improve levels of service
- Provide a **structured**, **documented approach** that ensures consistency and accountability.












**Stantec** 












- Observed climate trends over the past few decades indicate a changing climate. Since 1970, trends that have been observed include rising temperatures, more frequent hot days, longer growing seasons, less snowfall and more winter rain, reduced snowpack, and earlier ice and snowmelt resulting in earlier peak river flows.
- At Akwesasne, the drought of summer 2012 affected many of nature's cycles on all of creation. The changes came about in the way of hot and humid temperatures, high winds, heavy rainfall, hail, low water levels, and fish and wildlife reproductive cycles were out of sync. The downpour of rainfall, hail, and strong high winds destroyed gardens at a time when it was late to restart gardens to get a good crop. Some areas had 6 inches of hail in July. Thunderstorm warnings were also issued.





2020s


RSI

**Stantec** 













# Phase 2 - Development of the FN PIEVC/AM Toolkit

Funded by








Stantec



| TCA Reporting<br>(PS 3150) | Asset Management            | Risk Management                          | Corporation |
|----------------------------|-----------------------------|--|-------------|
| Inventory                  | Inventory                   | Inventory                                |             |
| Condition Assessment       | Condition Assessment        | Condition Assessment                     |             |
| (Physical Condition)       | (Physical Condition,        | (Physical Condition,                     |             |
|                            | Capacity, Functionality)    | Capacity, Functionality)                 |             |
| Residual Life Prediction   | Residual Life Prediction    | Residual Life Prediction                 |             |
| Valuation (Historical)     | Valuation (Replacement)     | Valuation (Replacement)                  |             |
|                            | Analysis:                   | Analysis:                                |             |
|                            | Needs: Capacity, Physical   | Threats                                  |             |
|                            | Condition, O&M              | Exposure                                 |             |
|                            |                             | Vulnerability                            |             |
|                            | Cost-Benefit                | Risks                                    |             |
|                            | Life-cycle Management Plans |  |             |
|                            | Additions and Upgrades      |  |             |
|                            | Replacement and             |  |             |
|                            | Refurbishment               |  |             |
|                            | Operations and              |  |             |
|                            | Maintenance                 |  |             |
| +                          | Risk Management             | +  |             |
| TCA Report                 | Investment Plan (Capital,   | <ul> <li>Risk Management plan</li> </ul> |             |
| -                          | O&M)                        |  |             |
|                            | Monitor, Report, Revise     | Monitor, Report, Revise                  | 🕥 Stai      |







| Infrastructure Components              | ACRS |            |             |               | ance                  |                        |     |      |                          |   |     |                                   | C    | lima | le E            | ler | me | nts       |      |   |   |       |        |     |
|--|------|------------|-------------|---------------|-----------------------|------------------------|-----|------|--------------------------|---|-----|-----------------------------------|------|------|-----------------|-----|----|-----------|------|---|---|-------|--------|-----|
|  | ¥    |            | Cons        | ider          | ation                 | 5                      | Te  | mper | ature                    |   | Tem | perat                             | ture |      | Blizza          | ard |    |           | Rair | ı |   | Clima | ate ev | ent |
|  |      | Structural | Operational | -unctionality | Environment<br>(Land) | Environment<br>(Water) | day |      | cutive<br>n temp<br>deg. |   | ten | nsec<br>iys wi<br>np. < ·<br>deg. | th   |      | icm s<br>nour j |     |    | day<br>ra |      |   |   |       | 5      |     |
|  |      | S          | ŏ           | Fu            | ů.                    | ц                      | Y/N | Ρ    | S                        | R | Y/N | P :                               | S R  | Y/N  | Ρ               | S   | R  | Y/N       | Ρ    | S | R | Y/N   | ΡS     | R   |
| Water Treatment Plant                  |      |            |             |               |                       |                        | ΙI  |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| <ul> <li>Building structure</li> </ul> |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Building envelope ←                  |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Roof                                 |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Foundations                          |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Process equipment                    |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| <ul> <li>HVAC system</li> </ul>        |      |            | 1           | 1             |                       |                        | Y   |      |                          |   | Y   |                                   |      | N    |                 |     |    | N         |      |   |   |       |        |     |
| - SCADA                                |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Communications                       |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Electricity                          |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Site services                        |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| <ul> <li>Access road</li> </ul>        |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| - Third party supplies                 |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| Administration and                     |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |
| Operations                             |      |            |             |               |                       |                        |     |      |                          |   |     |                                   |      |      |                 |     |    |           |      |   |   |       |        |     |

Г

# Rating scales

## Climate



Provide Example




Stantec


## Impacts on Infrastructure

| Score | Probat                        | oility       | Score | Descriptor    |
|-------|-------------------------------|--------------|-------|---------------|
|       | Method A                      | Method B     | 0     | No Effect     |
| 0     | Negligible<br>Not Applicable  | < 1 in 1,000 | 1     | Insignificant |
|       | l Balaka Haribaaka            |              | 2     | Minor         |
| 1     | Highly Unlikely<br>Improbable | 1 in 100     | 3     | Moderate      |
| 2     | Remotely Possible             | 1 in 20      | 4     | Major         |
| -     |                               | 1 11 20      | 5     | Catastrophic  |
| 3     | Possible<br>Occasional        | 1 in 10      |       |               |
| 4     | Somewhat Likely<br>Normal     | 1 in 5       |       |               |
| 5     | Likely<br>Frequent            | >1 in 2.5    |       |               |
|       |                               |              |       |               |

| Infrastructure                           | SS<br>SS |            |             |              | ince                  |                        |     |      |                         |   |     | (0   | Cur                           | ren | t) C | lim            | ate | e El | eme      | ent                               | S               |   |     |           |       |
|--|----------|------------|-------------|--------------|-----------------------|------------------------|-----|------|-------------------------|---|-----|------|-------------------------------|-----|------|----------------|-----|------|----------|-----------------------------------|-----------------|---|-----|-----------|-------|
| Components                               | Ĭ        |            | Cons        | ider         | ation                 | S                      | Ter | nper | ature                   | ÷ | Ter | nper | ratur                         | е   |      | Blizza         | ard |      |          | Rai                               | n               |   | Cli | mate<br>5 | event |
|  |          | Structural | Operational | unctionality | Environment<br>(Land) | Environment<br>(Water) | day |      | cutive<br>1 tem<br>leg. |   | c   | lays | ecutiv<br>with<br>< -30<br>g. |     |      | cm s<br>nour p |     |      | day<br>r | onse<br>/s witi<br>ainfa<br>> 100 | h tota<br>II of |   |     | 5         |       |
|  |          | s          | ŏ           | Fur          | Ë                     | Ë                      | Y/N | Ρ    | S                       | R | Y/N | Ρ    | S                             | R   | Y/N  | Ρ              | S   | R    | Y/N      | Ρ                                 | S               | R | Y/N | Ρ         | S R   |
| Water Treatment Plant                    |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Building structure</li> </ul>   |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Building envelope</li> </ul>    |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| - Roof                                   |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Foundations</li> </ul>          |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Process equipment</li> </ul>    |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>HVAC system</li> </ul>          |          |            | 1           | 1            |                       |                        | Y   | 1    | 3                       | 3 | Y   | 3    | 2                             | 6   | N    |                |     |      | N        |                                   |                 |   |     |           |       |
| - SCADA                                  |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Communications</li> </ul>       |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| - Electricity                            |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| - Site services                          |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Access road</li> </ul>          |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Third party supplies</li> </ul> |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| Administration and                       |          |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| Operations                               | 11 1     |            |             |              |                       |                        |     |      |                         |   |     |      |                               |     |      |                |     |      |          |                                   |                 |   |     |           |       |





| Infrastinfraste Components  | ACRS |            |             |               | ince                  |                        |           |                |       |    |           | (F                    | utu   | r <mark>e)</mark> C | lim            | ate   | Ele | eme            | nts                      |    |    |      |       |      |
|---|------|------------|-------------|---------------|-----------------------|------------------------|-----------|----------------|-------|----|-----------|-----------------------|-------|---------------------|----------------|-------|-----|----------------|--------------------------|----|----|------|-------|------|
| Components  | Ā    |            | Cons        | ider          | ation                 | S                      | Tei       | mper           | ature |    | Terr      | npera                 | ature |                     | Blizza         | ard   |     |                | Rair                     | ۱  |    | Clim | ate e | /ent |
|   |      | Structural | Operational | Functionality | Environment<br>(Land) | Environment<br>(Water) | day:<br>> | s with<br>30 d |       | p. | da<br>ter | ays w<br>np. <<br>deg | -30   | 24                  | i0cm :<br>hour | peric | d   | day<br>ra<br>> | s with<br>ainfal<br>100r | mm | el |      | 5     |      |
| Water Treatment Plant         -       Building structure         -       Building envelope         -       Roof         -       Foundations         -       Process equipment               |      |            | U           | Ľ             | ш                     | E                      | Y/N       | Ρ              | S     | R  | Y/N       | Ρ                     | S F   | Y/N                 | I P            | S     | R   | Y/N            | Ρ                        | S  | R  | Y/N  | Ρ     | S R  |
| - HVAC system   |      |            | 1           | 1             |                       |                        | Y         | 3              | 3     | 9  | Y         | 1                     | 2 2   | N                   |                |       |     | N              |                          |    |    |      |       |      |
| <ul> <li>SCADA</li> <li>Communications</li> <li>Electricity</li> <li>Site services</li> <li>Access road</li> <li>Third party supplies</li> <li>Administration and<br/>Operations</li> </ul> |      |            |             |               |                       |                        |           |                |       |    |           |                       |       |                     |                |       |     |                |                          |    |    |      |       |      |





|  | nfras                | struc         | ture           | Respor                      | ise Consid                                | eration |     | Ма          | x. Dai          | ly Ter          | np.          | Hote | est Mo<br>Ter                                 |                          | wg.)  | Lov          | v Prec<br>(Au               | cipitati<br>(q.)                        |                     | Com<br>Hiah  |                  | ion - A<br>. with |              |              | F     | og                          |               | Rai   | n - 7 c    | lay p         | iei |
|--|----------------------|---------------|----------------|-----------------------------|---|---------|-----|-------------|-----------------|-----------------|--------------|------|---|--------------------------|-------|--------------|-----------------------------|---|---------------------|--------------|------------------|-------------------|--------------|--------------|-------|-----------------------------|---------------|-------|------------|---------------|-----|
| Infrastructure Components                | Structural<br>Desian | Functionality | Serviceability | Watershed,<br>Surface Water | Operations,<br>Maintenance &<br>Materials | Effects |     | Days<br>Max | s (per<br>c Tem | year)<br>ps > 3 | with<br>86°C | Temp | y wari<br>os Mea<br>mer th<br>20 <sup>,</sup> | n Aug<br>an >2:<br>an Au | 2.5°C | tota<br>~50r | /s witl<br>I preci<br>mm (e | h Augu<br>ipitatio<br>qual to<br>h Augu | ust<br>on ≤<br>o or | Coml<br>Warn | binati<br>n Terr | on Au             | gust<br>ures | Fog v<br>½ s | tatut | lities I<br>e mile<br>ping) | oelow<br>(for | > 12( | 0 mm<br>da | rainfa<br>ays | al  |
|  | Marl                 | k Re          |                |                             | onses with                                |         |     | Y/N         | Р               | s               | R            | Y/N  | Ρ   | s                        | R     | Y/N          | Р                           | s                                       | R                   | Y/N          | Р                | s                 | R            | Y/N          | Р     | s                           | R             | Y/N   | Ρ          | s             |     |
| Cornwall Island                          |                      |               | 1              |                             | 1   | 1       | 1 1 |             | 5               |                 |              |      | 6   |                          |       |              | 5                           |   |                     |              | 4                |                   |              |              | 3     |                             |               |       | 3          | 1             | T   |
| Water Supply System                      |                      |               |                |                             |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Water Treatment Plant                    |                      |               |                |                             |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Building structure                       | 1                    |               |                |                             | ✓   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Building envelope                        | 1                    |               |                |                             | ✓   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Roof                                     | 1                    |               |                |                             | ✓   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Process equipment                        |                      | 1             | 1              |                             | 1   |         |     |             |                 |                 |              |      |   |                          |       |              |                             | 4                                       | 20                  |              |                  | 5                 | 20           |              |       |                             |               |       |            |               |     |
| HVAC system                              | 1                    | 1             | 1              |                             | ✓   |         |     |             |                 |                 |              |      |   | 3                        | 18    |              |                             |   |                     |              |                  | 3                 | 12           |              |       |                             |               |       |            |               |     |
| Foundations                              | 1                    |               |                |                             |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            | 1             |     |
| Site services                            | 1                    |               |                |                             | 1   | 1       |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Storage and/or alternate use             | 1                    | 1             | 1              |                             | 1   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            | 3             |     |
| Access road                              | 1                    | √             | √              |                             | <ul><li>✓</li></ul>                       |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Environment (plants, trees, animals)     |                      |               |                |                             |   | 1       |     |             |                 |                 |              |      |   | 3                        | 18    |              |                             |   | 25                  |              |                  | 6                 | 24           |              |       |                             |               |       |            |               |     |
| Environment (soil conditions)            |                      |               |                |                             |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             | 2                                       | 10                  |              |                  | 3                 | 12           |              |       |                             |               |       |            | 3             |     |
| Backwater disposal                       | 1                    | 1             |                |                             | 1   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Biosolids/sludge disposal                |                      |               | 1              |                             | <ul><li>✓</li></ul>                       |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Communications /<br>SCADA/Telemetry      | 1                    | 1             | 1              |                             | 1   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            |               |     |
| Back-up power (generator, fuel           | 1                    | 1             | 1              |                             | 1   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            | -             |     |
| storage)<br>WTP - High Lift Pumps        | 1                    | 1             | 1              |                             |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       |                             |               |       |            | +             | -   |
| WTP - High Lift Pumps<br>WTP - Reservoir | ~                    | 1<br>V        | ~              |                             | ~   |         |     |             |                 |                 |              |      |   |                          |       |              |                             | 5                                       | 25                  |              |                  | 5                 | 20           |              |       |                             |               |       |            |               | -   |
| WTP - Reservoir<br>WTP - Intake          | +                    |               | 1,             | -                           |   |         |     |             |                 |                 |              |      |   |                          |       |              |                             | 5                                       | 25                  |              |                  | 3                 | 20           |              |       |                             |               |       |            | ─             | -   |
| vv i m - intake                          | √                    | 1             | 1              | 1                           | + 5                                       | 1       |     |             |                 |                 |              |      |   |                          |       |              |                             |   |                     |              |                  |                   |              |              |       | 1                           | 1             |       | 1          | <u> </u>      | -   |

















































| /orkshop            | #3 - Agenda   | Corporation                               |   |
|---------------------|---|---|---|
| Time                | Description   |   |   |
| 9:30am – 9:45am     | Welcome and introductions   | Oneida Nation of the Thames<br>and OFNTSC |   |
| 9:45am – 10:30am    | Review of Workshop # 2 findings and<br>PIEVC Protocol steps and discussion        | Consultant                                |   |
| 10:30am – 10:45am   | Health break  |   | ł |
| 10:45am – 11:30am   | Presentation of preliminary climate<br>parameters and selection                   | Consultant; All                           |   |
| 11:30am – 12:00noon | Risk matrix: infrastructure and<br>climate interactions                           | All participants                          |   |
| 12:00pm – 12:45pm   | Lunch   |   | ĺ |
| 12:45pm – 3:30pm    | Risk matrix: climate events'<br>probabilities, severity rating and<br>risk scores | All participants                          |   |
| 3:30pm – 3:45pm     | Review and next steps   | Consultant                                |   |
| 3:30pm              | Adjourn   |   |   |



| Infrastructure Components   | ACRS |            |             |               | ince                  |                        |     |           |               |       |     |                   |                                     | Cl | ima  | te E            | ler   | me | nts      |                          |     |    |      |      |       |
|---|------|------------|-------------|---------------|-----------------------|------------------------|-----|-----------|---------------|-------|-----|-------------------|-------------------------------------|----|------|-----------------|-------|----|----------|--------------------------|-----|----|------|------|-------|
|   | ₹    |            | Cons        | ider          | ations                | 5                      |     | Ten       | npera         | ature | Te  | empe              | eratur                              | е  |      | Blizza          | ard   |    |          | Ra                       | in  |    | Clin | nate | event |
|   |      | Structural | Operational | -unctionality | Environment<br>(Land) | Environment<br>(Water) | ۱L  | days<br>> | with<br>30 de |       | t   | days<br>emp<br>de | secuti<br>s with<br>o. < -3!<br>eg. | 5  | 24 ł | )cm s<br>nour j | peric | bd | day<br>r | ys wit<br>ainfa<br>> 100 | )mm | al |      | 5    |       |
| Water Treatment Plant   |      |            | 0           | 3             | ш                     | ш                      |     | Y/N       | Ρ             | S R   | Y/N | I P               | S                                   | R  | Y/N  | Ρ               | S     | R  | Y/N      | Ρ                        | S   | R  | Y/N  | Р    | S R   |
| <ul> <li>Building structure</li> <li>Building envelope &lt;</li></ul> |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Roof  |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Foundations   |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Process equipment   |      |            |             |               |                       |                        | Ц   |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| <ul> <li>HVAC system</li> </ul>                                       |      |            | 1           | 1             |                       |                        |     | Y         |               |       | Y   |                   |                                     |    | N    |                 |       |    | N        |                          |     |    |      |      |       |
| - SCADA   |      |            |             |               |                       |                        | Π   |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Communications  |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Electricity   |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Site services   |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| <ul> <li>Access road</li> </ul>                                       |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| - Third party supplies  |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| Administration and  |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
| Operations  |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
|   |      |            |             |               |                       |                        |     |           |               |       |     |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |
|   |      |            |             |               |                       |                        | I L |           |               |       | 11  |                   |                                     |    |      |                 |       |    |          |                          |     |    |      |      |       |

# Rating scales

#### Climate



Provide Example




Stantec


#### Impacts on Infrastructure


| Probab                       | oility  | Score  | Descriptor  |
|------------------------------|---|--|---|
| Method A                     | Method B  | 0  | No Effect   |
| Negligible<br>Not Applicable | < 1 in 1,000  | 1  | Insignificant   |
| Highly Uplikoly              |   | 2  | Minor   |
| Improbable                   | 1 in 100  | 3  | Moderate  |
| Remotely Possible            | 1 in 20   | 4  | Major   |
| ,                            |   | 5  | Catastrophic  |
| Possible<br>Occasional       | 1 in 10   |  |   |
| Somewhat Likely<br>Normal    | 1 in 5  |  |   |
| Likely<br>Frequent           | >1 in 2.5   |  |   |
|                              | Method A<br>Negligible<br>Not Applicable<br>Highly Unlikely<br>Improbable<br>Remotely Possible<br>Occasional<br>Somewhat Likely<br>Normal<br>Likely | Negligible<br>Not Applicable< 1 in 1,000Highly Unlikely<br>Improbable1 in 100Remotely Possible1 in 20Possible<br>Occasional1 in 10Somewhat Likely<br>Normal1 in 5Likely>1 in 2.5 | Method AMethod B0Negligible<br>Not Applicable< 1 in 1,000 |

| Infrastructure                           | SS<br>SS |            |             |              | ince                  |                        |      |      |                         |   |     | (0   | Cur   | ren | t) C | lim            | ate | e El | eme      | ent                               | S               |   |     |           |       |
|--|----------|------------|-------------|--------------|-----------------------|------------------------|------|------|-------------------------|---|-----|------|-------|-----|------|----------------|-----|------|----------|-----------------------------------|-----------------|---|-----|-----------|-------|
| Components                               | Ĭ        |            | Cons        | ider         | ation                 | S                      | Ter  | nper | ature                   | ; | Ter | nper | ature | Э   |      | Blizza         | rd  |      |          | Rai                               | n               |   | Cli | mate<br>5 | event |
|  |          | Structural | Operational | unctionality | Environment<br>(Land) | Environment<br>(Water) | days |      | cutive<br>1 tem<br>leg. |   | c   | ays  | < -30 |     |      | cm s<br>nour p |     |      | day<br>r | onse<br>/s witi<br>ainfa<br>> 100 | h tota<br>II of |   |     | 5         |       |
|  |          | S          | ŏ           | Fur          | Ë                     | Ë                      | Y/N  | Ρ    | S                       | R | Y/N | Ρ    | S     | R   | Y/N  | Ρ              | S   | R    | Y/N      | Ρ                                 | S               | R | Y/N | Ρ         | S R   |
| Water Treatment Plant                    |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Building structure</li> </ul>   |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Building envelope</li> </ul>    |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| - Roof                                   |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Foundations</li> </ul>          |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Process equipment</li> </ul>    |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>HVAC system</li> </ul>          |          |            | 1           | 1            |                       |                        | Y    | 1    | 3                       | 3 | Y   | 3    | 2     | 6   | N    |                |     |      | N        |                                   |                 |   |     |           |       |
| - SCADA                                  |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Communications</li> </ul>       |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Electricity</li> </ul>          |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| - Site services                          |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Access road</li> </ul>          |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| <ul> <li>Third party supplies</li> </ul> |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| Administration and                       |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |
| Operations                               |          |            |             |              |                       |                        |      |      |                         |   |     |      |       |     |      |                |     |      |          |                                   |                 |   |     |           |       |





| Infrastinfraste Components  | ACRS |            |             |               | ince                  |                        |           |                |       |    |           | (F                    | utu   | r <mark>e)</mark> C | lim            | ate   | Ele | eme             | nts                      |    |    |      |       |      |
|---|------|------------|-------------|---------------|-----------------------|------------------------|-----------|----------------|-------|----|-----------|-----------------------|-------|---------------------|----------------|-------|-----|-----------------|--------------------------|----|----|------|-------|------|
| Components  | Ā    |            | Cons        | ider          | ation                 | S                      | Tei       | mper           | ature |    | Terr      | npera                 | iture |                     | Blizza         | ard   |     |                 | Rair                     | ۱  |    | Clim | ate e | /ent |
|   |      | Structural | Operational | Functionality | Environment<br>(Land) | Environment<br>(Water) | day:<br>> | s with<br>30 d |       | p. | da<br>ter | ays w<br>np. <<br>deg | -30   | 24                  | i0cm s<br>hour | perio | d   | day:<br>ra<br>> | s with<br>ainfal<br>100r | mm | el |      | 5     |      |
| Water Treatment Plant         -       Building structure         -       Building envelope         -       Roof         -       Foundations         -       Process equipment               |      |            | U           | Ľ             | ш                     | E                      | Y/N       | Ρ              | S     | R  | Y/N       | Ρ                     | S R   | Y/N                 | I              | S     | R   | Y/N             | Ρ                        | S  | R  | Y/N  | Ρ     | S R  |
| - HVAC system   |      |            | 1           | 1             |                       |                        | Y         | 3              | 3     | 9  | Y         | 1                     | 2 2   | N                   |                |       |     | N               |                          |    |    |      |       |      |
| <ul> <li>SCADA</li> <li>Communications</li> <li>Electricity</li> <li>Site services</li> <li>Access road</li> <li>Third party supplies</li> <li>Administration and<br/>Operations</li> </ul> |      |            |             |               |                       |                        |           |                |       |    |           |                       |       |                     |                |       |     |                 |                          |    |    |      |       |      |




















## 6. Impacts from Neighbouring Communities








[To be confirmed] With respect to the infrastructure or infrastructure component being assessed, climate loading may have impacts on neighbouring communities which may affect:


- Water source
- Drainage
- Regional Landfill
- Other


| Cl   | imate                        |              | lm    | pacts on      | Infrastructure  | Ż |
|------|------------------------------|--------------|-------|---------------|-----------------|---|
| core | Probab                       | •            | Score | Descriptor    | Provide Example |   |
|      | Method A                     | Method B     | 0     | No Effect     |                 |   |
| 0    | Negligible<br>Not Applicable | < 1 in 1,000 | 1     | Insignificant |                 |   |
|      | Highly Unlikely              |              | 2     | Minor         |                 |   |
| 1    | Improbable                   | 1 in 100     | 3     | Moderate      |                 |   |
| 2    | Remotely Possible            | 1 in 20      | 4     | Major         |                 |   |
|      | ,                            |              | 5     | Catastrophic  |                 |   |
| 3    | Possible<br>Occasional       | 1 in 10      |       |               |                 |   |
| 4    | Somewhat Likely<br>Normal    | 1 in 5       |       |               |                 |   |


































| D:6137    | 260   |       |       |       | Corporation |        |
|-----------|-------|-------|-------|-------|-------------|--------|
|           |       |       |       |       |             |        |
| Historic  | a     |       |       |       |             |        |
| T (years) | 2     | 5     | 10    | 25    | 50          | 100    |
| 5 min     | 8.25  | 11.02 | 13.04 | 15.82 | 18.07       | 20.47  |
| 10 m in   | 12.26 | 16.28 | 18.85 | 22.00 | 24.28       | 26.47  |
| 15 min    | 14.87 | 19.91 | 23.13 | 27.08 | 29.92       | 32.67  |
| 30 m in   | 20.12 | 26.99 | 31.48 | 37.10 | 41.21       | 45.27  |
| 1 h       | 25.59 | 34.75 | 40.58 | 47.69 | 52.79       | 57.71  |
| 2 h       | 29.70 | 41.19 | 49.44 | 60.65 | 69.58       | 78.99  |
| 6 h       | 37.78 | 51.28 | 61.63 | 76.58 | 89.20       | 103.19 |
| 12 h      | 43.67 | 58.81 | 69.82 | 84.95 | 97.14       | 110.11 |
| 24 h      | 49.29 | 66.81 | 79.34 | 96.31 | 109.77      | 123.92 |

| D:6137<br>035 – | ′362<br>2065 – | RCP   | 4.5   |        | Corporation | Ň      |
|-----------------|----------------|-------|-------|--------|-------------|--------|
| T (years)       | 2              | 5     | 10    | 25     | 50          | 100    |
| 5 min           | 9.21           | 12.59 | 15.48 | 19.06  | 21.66       | 24.66  |
| 10 m in         | 13.95          | 18.71 | 22.48 | 26.52  | 29.20       | 32.17  |
| 15 min          | 16.92          | 22.88 | 27.58 | 32.63  | 35.99       | 39.69  |
| 30 min          | 22.90          | 31.02 | 37.52 | 44.70  | 49.51       | 54.94  |
| 1 h             | 29.12          | 39.94 | 48.41 | 57.49  | 63.54       | 70.12  |
| 2 h             | 33.18          | 47.10 | 58.76 | 73.10  | 83.49       | 95.31  |
| 6 h             | 42.27          | 58.53 | 72.95 | 92.30  | 106.91      | 123.63 |
| 12 h            | 48.79          | 67.20 | 82.91 | 102.36 | 116.44      | 132.69 |
| 24 h            | 55.06          | 76.38 | 94.28 | 116.04 | 131.63      | 149.62 |


























| Rating | Sco   | ale - Climo                   | ate               | Ontario First Nations<br>Technical Services<br>Corporation |      |
|--------|-------|-------------------------------|-------------------|--|------|
|        | Score | Probab<br>Method A            | ility<br>Method B |  |      |
|        |       | Method A                      | Method B          |  |      |
|        | 0     | Negligible<br>Not Applicable  | < 1 in 1,000      |  |      |
|        | 1     | Highly Unlikely<br>Improbable | 1 in 100          |  |      |
|        | 2     | Remotely Possible             | 1 in 20           |  |      |
|        | 3     | Possible<br>Occasional        | 1 in 10           |  |      |
|        | 4     | Somewhat Likely<br>Normal     | 1 in 5            |  |      |
|        | 5     | Likely<br>Frequent            | >1 in 2.5         | 🚺 Sta  | ntec |


| Score and<br>Description | Consequence [Structural, Functional, Operations]  | Ontario First Nations |
|--------------------------|---|-----------------------|
| 0<br>No effect           | <ul> <li>No damage</li> <li>Continues to perform as intended</li> <li>Fully operational – normal</li> </ul>   | Corporation           |
| 1<br>Insignificant       | Can be corrected through the regular maintenance cycle  |                       |
| 2<br>Minor               | <ul><li>Requires sending repair crew</li><li>No replacement of asset necessary</li><li>May need further assessment</li></ul>  | <b>Rating Scale -</b> |
| 3<br>Moderate            | <ul> <li>Needs attention</li> <li>Requires sending repair crew</li> <li>Needs replacement of components</li> <li>Might need to order parts</li> <li>Will need further assessment</li> </ul>   | Infrastructure        |
| 4<br>Major               | <ul><li>Collapse/total loss of asset or components</li><li>Little or no impacts on other elements</li></ul>   |                       |
| 5<br>Catastrophic        | <ul> <li>Collapse</li> <li>Total loss of equipment and service that requires full replacement of asset, several assets and major components</li> <li>Will require relocating people/function</li> <li>Impacts on other elements of asset or other assets</li> <li>May have impacts on the public health and safety</li> </ul> | Stantec               |



























| Rating | Sco   | ale - Climo                   | ate                | Ontario First Nations<br>Technical Services<br>Corporation | of the name |
|--------|-------|-------------------------------|--------------------|--|-------------|
|        | Score | Probal<br>Method A            | bility<br>Method B |  |             |
|        | 0     | Negligible<br>Not Applicable  | < 1 in 1,000       |  |             |
|        | 1     | Highly Unlikely<br>Improbable | 1 in 100           |  |             |
|        | 2     | Remotely Possible             | 1 in 20            |  |             |
|        | 3     | Possible<br>Occasional        | 1 in 10            |  |             |
|        | 4     | Somewhat Likely<br>Normal     | 1 in 5             |  |             |
|        | 5     | Likely<br>Frequent            | >1 in 2.5          | 3  | Stantec     |

Ontario First Nations Technical Services Corporation



# Climate Parameters (Current Climate)

| M              | lax. | . Tem | p | N   | /lax. | Tem                     | p   |     |            | al Te<br>aions                  |     |     | w   | ind            |    |     | Torn  | nado  |   | Fr  | eezii | ng Ra                  | in |     | Ra    | ain                        |     | 3 day |                | nsecu<br>r rain |           |
|----------------|------|-------|---|-----|-------|-------------------------|-----|-----|------------|---------------------------------|-----|-----|-----|----------------|----|-----|-------|-------|---|-----|-------|------------------------|----|-----|-------|----------------------------|-----|-------|----------------|-----------------|-----------|
| 10 Da<br>>30 d |      |       |   | Day | s wit | ences<br>th Tei<br>3 da | mp. | со  | oling<br>d | ng an<br>g deg<br>ays<br>nt: 29 | ree | E   |     | ding 9<br>.p.h | 90 | C   | )escr | iptio | n |     | usin  | d 15<br>g loc<br>e dar | al | Hi  | gh Ir | uratio<br>Itensi<br>in 30r | ity | Tł    | iresh<br>ither |                 | or<br>ing |
| Y/N            | Р    | S     | R | Y/N | Р     | S                       | R   | Y/N | Р          | S                               | R   | Y/N | Р   | S              | R  | Y/N | Р     | s     | R | Y/N | Р     | S                      | R  | Y/N | Р     | S                          | R   | Y/N   | Р              | S               | R         |
|                | 4    |       |   |     | 2     |                         |     |     | 4          |                                 |     |     | 3   |                |    |     | 2     |       |   |     | 3     |                        |    |     | 1     |                            |     |       | 4              |                 |           |
|                | 4    |       |   |     | Z     |                         |     |     | 4          |                                 |     |     | _ 3 |                |    |     | Z     |       | 1 |     | 3     |                        |    |     | 1     |                            |     |       | 4              |                 |           |

| core and<br>escription | Consequence [Structural, Functional, Operations]  | Ontario First Nations          |
|------------------------|---|--------------------------------|
| 0<br>No effect         | <ul> <li>No damage</li> <li>Continues to perform as intended</li> <li>Fully operational – normal</li> </ul>   | Rating Scale<br>Infrastructure |
| 1<br>Insignificant     | Can be corrected through the regular maintenance cycle  |                                |
| 2<br>Minor             | <ul> <li>Requires sending repair crew</li> <li>No replacement of asset necessary</li> <li>May need further assessment</li> </ul>  |                                |
| 3<br>Moderate          | <ul> <li>Needs attention</li> <li>Requires sending repair crew</li> <li>Needs replacement of components</li> <li>Might need to order parts</li> <li>Will need further assessment</li> </ul>   |                                |
| 4<br>Major             | <ul><li>Collapse/total loss of asset or components</li><li>Little or no impacts on other elements</li></ul>   |                                |
| 5<br>Catastrophic      | <ul> <li>Collapse</li> <li>Total loss of equipment and service that requires full replacement of asset, several assets and major components</li> <li>Will require relocating people/function</li> <li>Impacts on other elements of asset or other assets</li> <li>May have impacts on the public health and safety</li> </ul> |                                |





Stantec

## Application of the Draft FN PIEVC/AM Toolkit: Oneida Nation of the Thames

**Risk Summary** 

#### **Ontario First Nations** Technical Services **High risks** Corporation All facilities: Iornado - > warning -> envergency measures/play - Tornado (Seniors complex) - Wind: loose material around properties Seniors complex - use of salt -o where the deterioration Seniors complex - Maximum Temp. : HVAC -- Seniers walkway huaring -- Freezing rain: fuel, access road, backup L New rold - little classificity generator - Winter rain: access road Foundat " cracking around door areas - Backup guarator- new- no corperience. • Housing units - Asphalt shingles' roofs: wind - Freezing rain: fuel, drainage - Winter rain: drainage Stantec

